

OPERATOR: K.P. Kauffman Company Inc.

WELL: YOXALL FARMS #2

FIELD: SPINDLE

API # 05-123-07815

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/3/1973

COMP: 11/7/1973

STATUS: SI

WBD DATE: 9/12/2022

FTG:

Q-Q: SENW

SEC.: 28

TWS: 1N

RGE: 67W

BY:

### CURRENT WELLBORE DIAGRAM

KBE: 5004 '

KB: 8 '

GLE: 4996 '

TD (ft): 4978

PBTD (ft): 4937

12.25" Hole  
8.625" 24# Csg @ 211 '  
Cmtd w/200 sxs

TOC @ 2958 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 4977 '  
Cmtd w/400 sxs

SUSSEX Perfs  
4824'-4858'

PBTD (ft): 4937

TD (ft): 4978

#### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	211
7 7/8	4 1/2	10.5		0	4977

#### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

#### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4824	4858	94		