

OPERATOR: K.P. Kauffman Company Inc.

WELL: 1415 CORP GAS UNIT G #1

FIELD: SPINDLE

API # 05-123-10029

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 12/9/1980

COMP: 2/16/1981

STATUS: PR

WBD DATE: 9/14/2022

FTG:

Q-Q: SESW

SEC.: 14

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4950 '

KB: 10 '

GLE: 4940 '

TD (ft): 4775

PBTD (ft): 4732

12.25" Hole
8.625" 24# Csg @ 212 '
Cmtd w/200 sxs

DV TOOL @ 583 '
2000 gal Angel

TOC @ 3387 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4775 '
Cmtd w/275 sxs

SUSSEX Perfs
4600'-4642'

PBTD (ft): 4732 '

TD (ft): 4775 '

CASING RECORD

| HOLE (in) | SIZE (in) | WT (lb/ft) | GRADE | TOP (ft) | BTM (ft) |
|---------------|--------------|-------------|-------|----------|-------------|
| <u>12 1/4</u> | <u>8 5/8</u> | <u>24</u> | | <u>0</u> | <u>212</u> |
| <u>7 7/8</u> | <u>4 1/2</u> | <u>10.5</u> | | <u>0</u> | <u>4775</u> |

TUBING RECORD

| SIZE (in) | WT (lb/ft) | GRADE | JOINTS | BTM (ft) |
|-----------|------------|-------|--------|----------|
| | | | | |

PERFORATION RECORD

| ZONE | TOP (ft) | BTM (ft) | HOLES | STAGE | STATUS |
|---------------|-------------|-------------|------------|-------|--------|
| <u>SUSSEX</u> | <u>4600</u> | <u>4642</u> | <u>172</u> | | |