

OPERATOR: K.P. Kauffman Company Inc.

WELL: ALEX DONES UNIT #1

FIELD: SPINDLE

API # 05-123-08530

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 9/19/1975

COMP: 12/22/1975

STATUS: PR

WBD DATE: 9/14/2022

FTG:

Q-Q: NENW

SEC: 34

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5019 '

KB: 7 '

GLE: 5012 '

TD (ft): 5160 '

PBTD (ft): 5100 '

17.5" Hole

13.375" 36# Csg @ 166 '

Cmtd w/400 sxs

12.25" Hole

8.625" 24# Csg @ 532 '

Cmtd w/400 sxs

TOC @ 3645 '

Calc Assuming 1.15 yield

7.875" Hole

4.5" 10.5# Csg @ 5160 '

Cmtd w/300 sxs

SUSSEX Perfs
4578'-4590'

SHANNON Perfs
5018'-5037'

PBTD (ft): 5100 '

TD (ft): 5160 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>17 1/2</u>	<u>13 3/8</u>	<u>36</u>		<u>0</u>	<u>166</u>
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>532</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5160</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4578</u>	<u>4590</u>	<u>26</u>		
<u>SHANNON</u>	<u>5018</u>	<u>5037</u>	<u>40</u>		