

OPERATOR: K.P. Kauffman Company Inc.

WELL: BROZOVICK UNIT #2

FIELD: SPINDLE

API # 05-123-09144

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 2/28/1977

COMP: 6/1/1977

STATUS: PR

WBD DATE: 9/14/2022

FTG:

Q-Q: SENW

SEC.: 25

TWS: 2N

RGE: 68W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5003 '

KB: 12 '

GLE: 4991 '

TD (ft): 5115 '

PBTD (ft): 5081 '

12.25" Hole  
8.625" 24# Csg @  
Cmtd w/500 sxs

780 '

TOC @ 2831 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 5103 '  
Cmtd w/450 sxs

SUSSEX Perfs  
4556'-4598'

SHANNON Perfs  
4990'-5010'

PBTD (ft): 5081 '

TD (ft): 5115 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>780</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5103</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4556</u>	<u>4598</u>	<u>86</u>		
<u>SHANNON</u>	<u>4990</u>	<u>5010</u>	<u>42</u>		