

OPERATOR: K.P. Kauffman Company Inc.

WELL: C.E. WINGO #1

FIELD: SPINDLE

API # 05-123-08482

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/31/1975

COMP: 1/2/1976

STATUS: PR

WBD DATE: 9/14/2022

FTG:

Q-Q: NENE

SEC.: 12

TWS: 1N

RGE: 68W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5096 '

KB: 10 '

GLE: 5086 '

TD (ft): 5350 '

PBTD (ft): 5286 '

12.25" Hole  
8.625" 24# Csg @ 755 '  
Cmtd w/550 sxs

TOC @ 3835 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 5350 '  
Cmtd w/300 sxs

SUSSEX Perfs  
4764'-4790'

SHANNON Perfs  
5214'-5230'

PBTD (ft): 5286 '

TD (ft): 5350 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>755</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5350</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4764</u>	<u>4790</u>	<u>54</u>		
<u>SHANNON</u>	<u>5214</u>	<u>5230</u>	<u>34</u>		