

OPERATOR: K.P. Kauffman Company Inc.

WELL: JACK BERGER #4

FIELD: SPINDLE

API # 05-123-08826

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/26/1976

COMP: 9/16/1976

STATUS: PR

WBD DATE: 9/15/2022

FTG:

Q-Q: SENE

SEC.: 3

TWS: 1N

RGE: 67W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 4970 '

KB: 9 '

GLE: 4961 '

TD (ft): 4809

PBTD (ft): 4757

12.25" Hole  
8.625" 24# Csg @ 785 '  
Cmtd w/500 sxs

TOC @ 3799 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 4809 '  
Cmtd w/200 sxs

SUSSEX Perfs  
4654'-4694'

PBTD (ft): 4757 '

TD (ft): 4809 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>785</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4809</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4654</u>	<u>4694</u>	<u>56</u>		