

OPERATOR: K.P. Kauffman Company Inc.

WELL: MCDONALD UNIT #2

FIELD: SPINDLE

API # 05-123-09145

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 3/7/1977

COMP: 6/22/1977

STATUS: PR

WBD DATE: 9/15/2022

FTG:

Q-Q: NWSW

SEC.: 25

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4992 '

KB: 12 '

GLE: 4980 '

TD (ft): 5125

PBTD (ft): 5071

12.25" Hole
8.625" 24# Csg @ 792 '
Cmtd w/500 sxs

TOC @ 2843 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 5115 '
Cmtd w/450 sxs

SUSSEX Perfs
4563'-4596'

SHANNON Perfs
4986'-5012'

PBTD (ft): 5071 '

TD (ft): 5125 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>792</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5115</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4563</u>	<u>4596</u>	<u>68</u>		
<u>SHANNON</u>	<u>4986</u>	<u>5012</u>	<u>54</u>		