

OPERATOR: **K.P. Kauffman Company Inc.**

WELL: **PELTIER UNIT B #1**

FIELD: **SPINDLE**

API # **05-123-08491**

LEASE #:

UIC #:

CNTY: **DAcono/WELD**

STATE: **CO**

SPUD: **8/11/1975**

COMP: **2/18/1976**

STATUS: **SI**

WBD DATE: **9/15/2022**

FTG:

Q-Q: **NENE**

SEC.: **1**

TWS: **1N**

RGE: **68W**

BY:

## CURRENT WELLBORE DIAGRAM

KBE: **5039** '

KB: **9** '

GLE: **5030** '

TD (ft): **5258** '

PBTD (ft): **5221** '

12.25" Hole

8.625" 24# Csg @ **595** '

Cmtd w/425 sxs

TOC @ **3744** '

Calc Assuming 1.15 yield

7.875" Hole

4.5" 10.5# Csg @ **5259** '

Cmtd w/300 sxs

SUSSEX Perfs

4712'-4734'

SHANNON Perfs

5126'-5146'

PBTD (ft): **5221** '

TD (ft): **5258** '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<b>12 1/4</b>	<b>8 5/8</b>	<b>24</b>		<b>0</b>	<b>595</b>
<b>7 7/8</b>	<b>4 1/2</b>	<b>10.5</b>		<b>0</b>	<b>5259</b>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<b>SUSSEX</b>	<b>4712</b>	<b>4734</b>	<b>46</b>		
<b>SHANNON</b>	<b>5126</b>	<b>5146</b>	<b>42</b>		