

OPERATOR: K.P. Kauffman Company Inc.

WELL: RODGERS UNIT #2

FIELD: SPINDLE

API # 05-123-09154

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 5/14/1977

COMP: 8/4/1977

STATUS: PR

WBD DATE: 9/16/2022

FTG:

Q-Q: SENW

SEC.: 34

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5032 '

KB: 12 '

GLE: 5020 '

TD (ft): 5180

PBTD (ft): 5123

12.25" Hole

8.625" 24# Csg @ 796 '

Cmtd w/650 sxs

TOC @ 2896 '

Calc Assuming 1.15 yield

7.875" Hole

4.5" 11/10.5# Csg @ 5168 '

Cmtd w/450 sxs

SUSSEX Perfs
4594'-4630'

SHANNON Perfs
5028'-5036'

PBTD (ft): 5123 '

TD (ft): 5180 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	796
7 7/8	4 1/2	11/10.5		0	5168

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4594	4630	74		
SHANNON	5028	5036	18		