




COLORADO OIL AND GAS CONSERVATION COMMISSION SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

Notice of intention to drill (attach plat) _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report XXX

Locate Well Correctly

X			
		16	

Notice to do work ☒ Land: Fee and Patented ☐
 Report of work done ☐ State ☒

Lease No. 4734

COLORADO
State

ADAMS
County

CABIN CREEK
Field

11-16 HARTMAN STATE NW 16 3S 59W 6th
 (Well No.) (Lease) (1/4 Sec.) (Sec.) (Twp.) (Range) (Meridian)

The Well is located 330 Ft. ~~XXX~~ of Section Line and 330 Ft. (E) of
 Section Line. (S) ~~XXX~~

The elevation above sea level is 4972 KB Ft.

Details of Plan of Work: (State names of and expected depths to objective sands, show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Spudded: 1-24-55

10-3/4" cem 240' w/150 sax.

TD: 6248'

7" cem 6248' w/300 sax.

'J' Sand perforated 6171-74.

Completed 2-16-55 for IP 27 BOPD 35% cut.

Total oil produced 1339 bbls, no production since Sept 19, 1955.

Propose to plug and abandon well in the following manner:

1. Will place 10 sax plug with dump bailer from 6175' to 6125'.
2. Determine free point of 7" casing, shoot off and recover casing.
3. Place 50 sax plug at base of surface pipe at 240'.
4. Cut off casing 4' below ground level, place 10 sax plug in top of casing and weld steel plate on top of casing stub.

Note: Heavy mud to be left between cement plugs.

Approved: NOV 9 1955

Date November 8, 1955

Company The Superior Oil Company

Address P. O. Box 200, Casper, Wyo.

By W.H. Farnham

Title Engineer

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

oil well now P-9.