

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 43 PAN AM I #8

FIELD: SPINDLE

API # 05-123-09019

LEASE #:

UIC #:

CNTY: DACONO/WELD

STATE: CO

SPUD: 10/28/1976

COMP: 3/24/1977

STATUS: SI

WBD DATE: 9/19/2022

FTG:

Q-Q: SWNW

SEC.: 11

TWS: 1N

RGE: 68W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5052 '

KB: 10 '

GLE: 5042 '

TD (ft): 5319 '

PBTD (ft): 5293 '

12.25" Hole

8.625" 24# Csg @ 669 '

Cmtd w/500 sxs

TOC @ 4057 '

Calc Assuming 1.15 yield

7.875" Hole

4.5" 10.5# Csg @ 5319 '

Cmtd w/250 sxs

SUSSEX Perfs

4722'-4742'

SHANNON Perfs

5180'-5194'

PBTD (ft): 5293 '

TD (ft): 5319 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>669</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5319</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4722</u>	<u>4742</u>	<u>42</u>		
<u>SHANNON</u>	<u>5180</u>	<u>5194</u>	<u>30</u>		