

OPERATOR: K.P. Kauffman Company Inc.

WELL: DORIS ACKERSON UNIT #1

FIELD: SPINDLE

API # 05-123-07578

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/26/1972

COMP: 1/11/1973

STATUS: PR

WBD DATE: 9/20/2022

FTG:

Q-Q: SWNE

SEC.: 11

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4980 '

KB: 8 '

GLE: 4972 '

TD (ft): 4840

PBTD (ft): 4790

12.25" Hole
8.625" 23# Csg @ 229 '
Cmtd w/200 sxs

TOC @ 2812 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 11.6/10.5# Csg @ 4831 '
Cmtd w/400 sxs

SUSSEX Perfs
4686'-4727'

PBTD (ft): 4790 '

TD (ft): 4840 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>23</u>		<u>0</u>	<u>229</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>11.6/10.5</u>		<u>0</u>	<u>4831</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4686</u>	<u>4727</u>	<u>20</u>		