

OPERATOR: K.P. Kauffman Company Inc.

WELL: FRISBIE #3

FIELD: SPINDLE

API # 05-123-08717

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 6/9/1976

COMP: 6/26/1976

STATUS: PR

WBD DATE: 9/20/2022

FTG:

Q-Q: NENE

SEC.: 30

TWS: 1N

RGE: 67W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5102 '

KB: 10 '

GLE: 5092 '

TD (ft): 5146 '

PBTD (ft): 5086 '

TOC @ 48 '

Calc Assuming 1.15 yield

12.25" Hole

8.625" 24# Csg @ 152 '

Cmtd w/140 sxs

DV TOOL @ 1049 '

Cmtd w/ 200 sxs

TOC @ 4389 '

Calc Assuming 1.15 yield

7.875" Hole

4.5" 10.5/9.5# Csg @ 5146 '

Cmtd w/150 sxs

SUSSEX Perfs

4816'-4882'

PBTD (ft): 5086 '

TD (ft): 5146 '

### CASING RECORD

| HOLE (in)     | SIZE (in)    | WT (lb/ft)      | GRADE | TOP (ft) | BTM (ft)    |
|---------------|--------------|-----------------|-------|----------|-------------|
| <u>12 1/4</u> | <u>8 5/8</u> | <u>24</u>       |       | <u>0</u> | <u>152</u>  |
| <u>7 7/8</u>  | <u>4 1/2</u> | <u>10.5/9.5</u> |       | <u>0</u> | <u>5146</u> |

### TUBING RECORD

| SIZE (in) | WT (lb/ft) | GRADE | JOINTS | BTM (ft) |
|-----------|------------|-------|--------|----------|
|           |            |       |        |          |

### PERFORATION RECORD

| ZONE          | TOP (ft)    | BTM (ft)    | HOLES      | STAGE | STATUS |
|---------------|-------------|-------------|------------|-------|--------|
| <u>SUSSEX</u> | <u>4816</u> | <u>4882</u> | <u>124</u> |       |        |