

OPERATOR: **K.P. Kauffman Company Inc.**

WELL: **JAMES S HALEY TRUSTEE B #2**

FIELD: **SPINDLE**

API #: **05-123-08651**

LEASE #:

UIC #:

CNTY: **DAcono/WELD**

STATE: **CO**

SPUD: **4/6/1976**

COMP: **6/15/1976**

STATUS: **SI**

WBD DATE: **9/21/2022**

FTG:

Q-Q: **SWSW**

SEC.: **2**

TWS: **1N**

RGE: **68W**

BY:

## CURRENT WELLBORE DIAGRAM

KBE: **5055'**

KB: **10'**

GLE: **5045'**

TD (ft): **5275'**

PBTD (ft): **5231'**

12.25" Hole

8.625" 24# Csg @ **622'**

Cmtd w/550 sxs

TOC @ **3759'**

Calc Assuming 1.15 yield

7.875" Hole

4.5" 11.6# Csg @ **5274'**

Cmtd w/300 sxs

SUSSEX Perfs  
4718'-4748'

SHANNON Perfs  
5164'-5184'

PBTD (ft): **5231'**

TD (ft): **5275'**

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	622
7 7/8	4 1/2	11.6		0	5274

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4718	4748	62		
SHANNON	5164	5184	42		