



# Donnelly Casing Pulling Co.

P.O. Box 791  
Sterling, Colorado 80751

Bob Donnelly

SOLD TO E. Doyle Huckabay, Ltd.  
1706 Security Life Bldg.  
Denver, Colorado 80202

RECEIVED

MAR 28 1977

INVOICE DATE 3-9-77

WELL Amoco Price #1-21

COIL ON & GAS CONS. COMM.

INVOICE NO. 201

3735' 4 1/4" OD Casing @  
Day Work, 63 hours @  
Cement, 15 sacks @  
7 shots, first 3 free,  
additional 4 @  
Pump, 2 jobs @  
Water Truck, 28 hours @  
Water, 1 load @  
Schmitt Reddi-Mix

DATE	DAY WORK	REMARKS
2- 7-77	0 hours	Moved rig to location.
2- 8-77	6 hours	Raised mast. Dug deadmen. Raised poles. Dug cellar.
2- 9-77	10 hours	Ran sand to 6080'. Set in jacks and worked pipe to 42'. Dumped 5 sacks cement on sand at 6080'. Shot at 5200'. Water truck, 4 hours.
2-10-77	8 hours	Worked pipe to 43". Shot at 5100'. Worked pipe to 45".
2-11-77	8 hours	Worked pipe at 45". Pumped 100 bbl. water around casing, but couldn't pump loose. Water truck, 6 hours. One load water.
2-14-77	10 hours	Spotted oil. Pumped 50 bbl. oil and displaced with 125 bbl. water. Pump job. Water truck, 10 hours.
2-15-77	5 hours	Worked pipe at 45".
2-18-77	7 hours	Worked pipe. Shot at 4800', 4500', 4300', 4100', 3900' and 3700'. Worked loose. Pulled 25 joints.
2-21-77	5 hours	Pumped oil out of hole. Pulled 75 joints. Water truck, 5 hours.
2-22-77	4 hours	Pulled casing to 250'. Pumped 50 sacks cement out casing to 100'. Pulled rest of casing, 124 in all. Talled pipe. Set 10 sacks cement in top of 8 5/8". Lowered poles. Water truck, 3 hours. Pump job.

WELL COMPLETE

THANK YOU

All open account are due by 10th of month following purchase. All amounts 30 days past due will be charged a FINANCE CHARGE at 1 1/2% per month or an ANNUAL PERCENTAGE RATE of 18%.