

OPERATOR: K.P. Kauffman Company Inc.

WELL: MILTON H. NELSON 'E' #1

FIELD: SPINDLE

API # 05-123-09620

LEASE #:

UIC #:

CNTY: FREDERICK/WELD

STATE: CO

SPUD: 10/16/1978

COMP: 2/15/1979

STATUS: SI

WBD DATE: 9/23/2022

FTG:

Q-Q: SWNE

SEC.: 29

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4927 '

KB: 12 '

GLE: 4915 '

TD (ft): 4940

PBTD (ft): 4888 '

12.25" Hole
8.625" 24# Csg @ 558 '
Cmtd w/425 sxs

TOC @ 2478 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4497 '
Cmtd w/400 sxs

SUSSEX Perfs
4372'-4398'

SHANNON Perfs
4818'-4834'

PBTD (ft): 4888 '

TD (ft): 4940 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>558</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4497</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4372</u>	<u>4398</u>	<u>54</u>		
<u>SHANNON</u>	<u>4818</u>	<u>4834</u>	<u>34</u>		