

OPERATOR: K.P. Kauffman Company Inc.
WELL: TOM L. RUSSELL #2
FIELD: SPINDLE
API # 05-123-08816
LEASE #: _____
UIC #: _____

CNTY: FIRESTONE/WELD FTG: _____
STATE: CO Q-Q: SENE
SPUD: 7/15/1976 SEC.: 30
COMP: 12/30/1976 TWS: 2N
STATUS: PR RGE: 67W
WBD DATE: 9/29/2022 BY: _____

CURRENT WELLBORE DIAGRAM

KBE: 5032 '
KB: 10 '
GLE: 5022 '

TD (ft): 5140 '
PBD (ft): 5101 '

12.25" Hole
8.625" 24# Csg @ 602 '
Cmtd w/500 sxs

TOC @ 3635 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 5150 '
Cmtd w/300 sxs

SUSSEX Perfs
4570'-4620'

SHANNON Perfs
5010'-5040'

PBD (ft): 5101 '
TD (ft): 5140 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>602</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5150</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4570</u>	<u>4620</u>	<u>102</u>		
<u>SHANNON</u>	<u>5010</u>	<u>5040</u>	<u>62</u>		