

OPERATOR: K.P. Kauffman Company Inc.

WELL: HANKINS #1

FIELD: SPINDLE

API # 05-123-09558

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 8/2/1978

COMP: 4/8/1981

STATUS: SI

WBD DATE: 10/3/2022

FTG:

Q-Q: SESE

SEC.: 19

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4968 '

KB: 7 '

GLE: 4961 '

TD (ft): 4920 '

PBTD (ft): 4855 '

12.25" Hole
8.625" 24# Csg @ 550 '
Cmtd w/450 sxs

TOC @ 3405 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4920 '
Cmtd w/300 sxs

SUSSEX Perfs
4351'-4388'

SHANNON Perfs
4790'-4806'

PBTD (ft): 4855 '

TD (ft): 4920 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>550</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4920</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4351</u>	<u>4388</u>	<u>76</u>		
<u>SHANNON</u>	<u>4790</u>	<u>4806</u>	<u>68</u>		