

OPERATOR: K.P. Kauffman Company Inc.

WELL: P.J. JACOBUECCI #B-2

FIELD: SPINDLE

API # 05-123-09957

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 6/11/1980

COMP: 8/9/1980

STATUS: PR

WBD DATE: 10/4/2022

FTG:

Q-Q: SESE

SEC.: 30

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5062 '

KB: 10 '

GLE: 5052 '

TD (ft): 5029

PBTD (ft): 4975

12.25" Hole
8.625" 24# Csg @ 214 '
Cmt'd w/200 sxs

DV TOOL @ 980 '
(Cmt vol not rpt'd)

TOC @ 4019 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 5029 '
Cmt'd w/200 sxs

SUSSEX Perfs
4852'-4922'

PBTD (ft): 4975 '

TD (ft): 5029 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>214</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5029</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4852</u>	<u>4922</u>	<u>284</u>		