

OPERATOR: K.P. Kauffman Company Inc.

WELL: P.J. JACOBUECCI #B-3

FIELD: SPINDLE

API # 05-123-10101

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/12/1980

COMP: 12/4/1980

STATUS: PR

WBD DATE: 10/4/2022

FTG:

Q-Q: NWSE

SEC.: 30

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5092 '

KB: 11 '

GLE: 5081 '

TD (ft): 5025

PBTD (ft): 4982

12.25" Hole
8.625" 24# Csg @ 249 '
Cmtd w/200 sxs

DV TOOL @ 778 '
2000 gal Angel

TOC @ 4015 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 15.5# Csg @ 5025 '
Cmtd w/200 sxs

SUSSEX Perfs
4833'-4908'

PBTD (ft): 4982 '

TD (ft): 5025 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>249</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>15.5</u>		<u>0</u>	<u>5025</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4833</u>	<u>4908</u>	<u>304</u>		