

OPERATOR: K.P. Kauffman Company Inc.

WELL: P.J. JACOBUECCI #B-4

FIELD: SPINDLE

API # 05-123-10100

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/16/1980

COMP: 12/13/1980

STATUS: PR

WBD DATE: 10/4/2022

FTG:

Q-Q: SWSE

SEC.: 30

TWS: 1N

RGE: 67W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5079 '

KB: 10 '

GLE: 5069 '

TD (ft): 5040

PBTD (ft): 4986

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>242</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>15.5</u>		<u>0</u>	<u>5040</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4832</u>	<u>4910</u>	<u>316</u>		

12.25" Hole  
8.625" 24# Csg @ 242 '  
Cmt'd w/200 sxs

STAGE TOOL @ 767 '  
(Cmt vol not rpt'd)

TOC @ 4030 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 15.5# Csg @ 5040 '  
Cmt'd w/200 sxs

SUSSEX Perfs  
4832'-4910'

PBTD (ft): 4986 '

TD (ft): 5040 '