

OPERATOR: K.P. Kauffman Company Inc.

WELL: RUEBEL ET AL #1-3

FIELD: WATTENBERG

API # 05-001-08732

LEASE #:

UIC #:

CNTY: ADAMS

STATE: CO

SPUD: 9/22/1985

COMP: 11/7/1985

STATUS: PR

WBD DATE: 10/4/2022

FTG:

Q-Q: NWNW

SEC: 1

TWS: 1S

RGE: 65W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5106 '

KB: 12 '

GLE: 5094 '

TD (ft): 7940

PBTD 7897

12.25" Hole
8.625" 24# Csg @ 221 '
Cmtd w/215 sxs

STAGE TOOL @ 1186 '
Cmtd w/ 280 sxs
TOC @ Surface
Calc Assuming 1.15 yield

TOC @ 6047 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 11.6# Csg @ 7940 '
Cmtd w/375 sxs

D SAND Perfs
7759'-7763'

J SAND Perfs
7819'-7853'

PBTD 7897 '
TD (ft): 7940

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	221
7 7/8	4 1/2	11.6		0	7940

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
D SAND	7759	7763	9		
J SAND	7819	7853	19		