

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 23 PAN AM M #2

FIELD: TRAPPER

API # 05-001-07499

LEASE #:

UIC #:

CNTY: ADAMS

STATE: CO

SPUD: 2/11/1980

COMP: 6/25/1980

STATUS: SI

WBD DATE: 10/10/2022

FTG:

Q-Q: NESE

SEC.: 19

TWS: 1S

RGE: 64W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5174 '

KB: 11 '

GLE: 5163 '

TD (ft): 8000

PBTD (ft): 7964

12.25" Hole
8.625" 24# Csg @ 235 '
Cmtd w/300 sxs

DV TOOL @ 1300 '
2000 gal Angel

TOC @ 6672 '
Calc Assuming 1.15 yield

7.875" Hole
5.5" 14# Csg @ 8000 '
Cmtd w/200 sxs

J SAND Perfs
7896'-7906'

PBTD (ft): 7964 '

TD (ft): 8000 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>235</u>
<u>7 7/8</u>	<u>5 1/2</u>	<u>14</u>		<u>0</u>	<u>8000</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>J SAND</u>	<u>7896</u>	<u>7906</u>	<u>44</u>		