

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 43 PAN AM I #11

FIELD: SPINDLE

API # 05-123-09114

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 2/2/1977

COMP: 6/30/1977

STATUS: SI

WBD DATE: 10/10/2022

FTG:

Q-Q: NWSE

SEC.: 11

TWS: 1N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5055 '

KB: 10 '

GLE: 5045 '

TD (ft): 5346 '

PBTD (ft): 5302 '

12.25" Hole
8.625" 24# Csg @ 690 '
Cmtd w/500 sxs

TOC @ 3317 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 5336 '
Cmtd w/400 sxs

SUSSEX Perfs
4722'-4738'

SHANNON Perfs
5190'-5210'

PBTD (ft): 5302 '

TD (ft): 5346 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>690</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5336</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4722</u>	<u>4738</u>	<u>34</u>		
<u>SHANNON</u>	<u>5190</u>	<u>5210</u>	<u>42</u>		