

OPERATOR: K.P. Kauffman Company Inc.

WELL: YOXALL FARMS #8

FIELD: SPINDLE

API # 05-123-09196

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 5/4/1977

COMP: 6/6/1977

STATUS: PR

WBD DATE: 10/10/2022

FTG:

Q-Q: NWNE

SEC.: 28

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5001 '

KB: 12 '

GLE: 4989 '

TD (ft): 4988 '

PBTD (ft): 4956 '

12.25" Hole
8.625" 24# Csg @ 275 '
Cmtd w/225 sxs

DV TOOL @ 968 '
Cmtd w/ 350 sxs
TOC @ Surface
CALC

TOC @ 3461 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4976 '
Cmtd w/300 sxs

SUSSEX Perfs
4788'-4816'

PBTD (ft): 4956 '

TD (ft): 4988 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>275</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4976</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4788</u>	<u>4816</u>	<u>58</u>		