

OPERATOR: K.P. Kauffman Company Inc.

WELL: YOXALL FARMS #9

FIELD: SPINDLE

API # 05-123-09197

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 4/30/1977

COMP: 6/16/1977

STATUS: PR

WBD DATE: 10/10/2022

FTG:

Q-Q: SENE

SEC.: 28

TWS: 1N

RGE: 67W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5012 '

KB: 12 '

GLE: 5000 '

TD (ft): 4950

PBTD (ft): 4909

12.25" Hole  
8.625" 24# Csg @ 820 '  
Cmtd w/600 sxs

TOC @ 3676 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 4938 '  
Cmtd w/250 sxs

SUSSEX Perfs  
4818'-4834'

PBTD (ft): 4909

TD (ft): 4950

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	820
7 7/8	4 1/2	10.5		0	4938

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4818	4834	34		