

OPERATOR: K.P. Kauffman Company Inc.

WELL: ALFRED HERMAN UNIT #2

FIELD: SPINDLE

API # 05-123-08903

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 8/28/1976

COMP: 11/23/1976

STATUS: PR

WBD DATE: 10/10/2022

FTG:

Q-Q: SWSE

SEC.: 7

TWS: 2N

RGE: 66W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4854 '

KB: 10 '

GLE: 4844 '

TD (ft): 4710

PBTD (ft): 4611

12.25" Hole
8.625" 24# Csg @ 662 '
Cmtd w/600 sxs

TOC @ 3700 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4710 '
Cmtd w/200 sxs

SUSSEX Perfs
4530'-4550'

PBTD (ft): 4611

TD (ft): 4710

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	662
7 7/8	4 1/2	10.5		0	4710

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4530	4550	42		