

OPERATOR: K.P. Kauffman Company Inc.

WELL: DEVORE #4

FIELD: SPINDLE

API # 05-123-09271

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 9/1/1977

COMP: 11/25/1977

STATUS: PR

WBD DATE: 10/11/2022

FTG:

Q-Q: NWSE

SEC.: 14

TWS: 2N

RGE: 67W

BY:

### CURRENT WELLBORE DIAGRAM

KBE: 4929 '

KB: 10 '

GLE: 4919 '

TD (ft): 4734

PBTD (ft): 4688

12.25" Hole  
8.625" 24# Csg @ 220 '  
Cmtd w/175 sxs

STAGE TOOL @ 617 '  
1000 gal Angel

TOC @ 3470 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 4732 '  
Cmtd w/250 sxs

SUSSEX Perfs  
4572'-4610'

PBTD (ft): 4688 '

TD (ft): 4734 '

#### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>220</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4732</u>

#### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

#### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4572</u>	<u>4610</u>	<u>68</u>		