

OPERATOR: K.P. Kauffman Company Inc.

WELL: JOHN HORST B #1

FIELD: SPINDLE

API # 05-123-09367

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 12/27/1977

COMP: 3/2/1978

STATUS: SI

WBD DATE: 10/12/2022

FTG:

Q-Q: NWNE

SEC.: 28

TWS: 2N

RGE: 67W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5052 '

KB: 10 '

GLE: 5042 '

TD (ft): 4817 '

PBTD (ft): 4731 '

12.25" Hole  
8.625" 24# Csg @ 653 '  
Cmtd w/400 sxs

TOC @ 3031 '  
Calc Assuming 1.15 yield

7.875" Hole  
5.5" 14# Csg @ 4690 '  
Cmtd w/250 sxs

SUSSEX Perfs  
4722'-4734'

PBTD (ft): 4731 '

TD (ft): 4817 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>653</u>
<u>7 7/8</u>	<u>5 1/2</u>	<u>14</u>		<u>0</u>	<u>4690</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4722</u>	<u>4734</u>	<u>26</u>		