

OPERATOR: K.P. Kauffman Company Inc.

WELL: NELS CHRISTIANSEN #1

FIELD: SPINDLE

API # 05-123-07687

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 4/2/1973

COMP: 5/6/1973

STATUS: PR

WBD DATE: 10/13/2022

FTG:

Q-Q: NWNE

SEC.: 17

TWS: 2N

RGE: 66W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4908 '

KB: 8 '

GLE: 4900 '

TD (ft): 4725

PBTD (ft): 4684

12.25" Hole
8.625" 24# Csg @ 214 '
Cmtd w/200 sxs

TOC @ 2706 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4725 '
Cmtd w/400 sxs

SUSSEX Perfs
4590'-4624'

PBTD (ft): 4684 '

TD (ft): 4725 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>214</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4725</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4590</u>	<u>4624</u>	<u>86</u>		