

Ranger Energy Services, LLC
10350 Richmond Avenue Suite 550
Houston, TX 77042
(713) 935-8900
(713) 935-8901 (FAX)



491322

Unit # C1003

Daily Work Ticket

Day # 11

Customer Name	Customer AFE #	Date:
Chevron	DNP	11/11/2022

Mailing Address	City	State	Zip	County
		CO		Weld County, CO

Field	Lease	Well	Order #
		HOWE-USX AB 33-6	
TVD	MD	Calculated Horizontal Length	Company Rep
00	00	0	Patricia Albidrez

Work Description	
P&A	<input checked="" type="checkbox"/>

Sub Code Description	
Cement	<input checked="" type="checkbox"/>

Description	Qty	Rate	Disc	Total	Stage
Turnkey Rigless Cement Pump Charge					
Wireline Charge					
Wireline Gauge Ring Charge					
Water Bobtail Hours					
Cement Retarder					
Cement Defoamer					
Cement (neat)					
Sugar					

Description of Work	Start Time 07:00 AM	Stop Time 05:00 PM
---------------------	---------------------	--------------------

From	To	Hours	Description	Details	Stage
7:00:00 AM	8:00:00 AM	1	RU/RD cement crew	(DNP) C1003 - Patricia Albidrez Gate to gate: 7:00 am – 5:00 pm MOB to location, spot in, rig up, waited on flowback to incinerate gas, 11:00 AM Stat	
8:00:00 AM	9:00:00 AM	1	RU/RD cement crew	us: 2-3/8" 4.7# tubing cut at 6,851' inside 4-1/2" 11.6# casing, pumped 32 bbls of freshwater, pumped 5 bbl. LCM pill, displaced with 25.7 bbls, wait	
9:00:00 AM	10:00:00 AM	1	RU/RD cement crew	ed 30 minutes, established circulation with 51 bbls of water, pumped 110 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 1	
10:00:00 AM	11:00:00 AM	1	RU/RD cement crew	.15 cu.ft./sack Class G cement with retarder, 7.2 bbls of slurry, displaced with 25.2 bbls to cover from 6,851' to 6,338', RD valve, wash out pump; 3:	
11:00:00 AM	5:00:00 PM	6	RU/RD cement crew	30 MOB to Yard Non rev: pre/post-trip trucks, prep for job, Cleaned out Patrick	

Payroll Section					
Employee	Rev Hours	Travel Hours	Non Rev Hours	Total	
Supervisor	Pena, Marcos	9.00	0.00	0.00	9.00
Operator	Meza, Abraham	10.00	0.00	0.00	10.00
Derrick	Soto, Juan I.	10.00	0.00	0.00	10.00

No Unreported Incidents Per My
Signature

Ranger Representative

Customer/Agent

