

OPERATOR: K.P. Kauffman Company Inc.

WELL: SACK #44-31

FIELD: SPINDLE

API # 05-123-15891

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/12/1992

COMP: 8/4/1992

STATUS: PR

WBD DATE: 10/13/2022

FTG:

Q-Q: SESE

SEC.: 31

TWS: 1N

RGE: 67W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 5065 '

KB: 12 '

GLE: 5053 '

TD (ft): 5031

PBTD (ft): 4992

12.25" Hole  
8.625" 24# Csg @ 308 '  
Cmt'd w/240 sxs

STAGE TOOL @ 1095 '  
(Cmt vol not rpt'd)

TOC @ 4310 '  
CBL

7.875" Hole  
4.5" 11.6/10.5# Csg @ 5029 '  
Cmt'd w/170 sxs

SUSSEX Perfs  
4896'-4908'

PBTD (ft): 4992 '

TD (ft): 5031 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>308</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>11.6/10.5</u>		<u>0</u>	<u>5029</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4896</u>	<u>4908</u>	<u>36</u>		