

OPERATOR: K.P. Kauffman Company Inc.

WELL: SIDNEY STREAR #3

FIELD: SPINDLE

API # 05-123-08961

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 10/2/1976

COMP: 12/13/1976

STATUS: PR

WBD DATE: 10/13/2022

FTG:

Q-Q: NWSW

SEC.: 23

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4979 '

KB: 12 '

GLE: 4967 '

TD (ft): 4814

PBTD (ft): 4763

12.25" Hole
8.625" 24# Csg @ 742 '
Cmtd w/550 sxs

TOC @ 3804 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4814 '
Cmtd w/200 sxs

SUSSEX Perfs
4650'-4688'

PBTD (ft): 4763 '

TD (ft): 4814 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	742
7 7/8	4 1/2	10.5		0	4814

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4650	4688	78		