

OPERATOR: K.P. Kauffman Company Inc.

WELL: SUCKLA G UNIT #1

FIELD: SPINDLE

API # 05-123-07821

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 8/24/1973

COMP: 9/21/1973

STATUS: PR

WBD DATE: 10/14/2022

FTG:

Q-Q: NENW

SEC.: 33

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5079 '

KB: 10 '

GLE: 5069 '

TD (ft): 4880

PBTD (ft): 4838

12.25" Hole
8.625" 24# Csg @ 218 '
Cmtd w/200 sxs

TOC @ 2861 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4880 '
Cmtd w/400 sxs

SUSSEX Perfs
4733'-4756'

PBTD (ft): 4838 '

TD (ft): 4880 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>218</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4880</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4733</u>	<u>4756</u>	<u>60</u>		