

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 23 PAN AM M #3

FIELD: TRAPPER

API # 05-001-07872

LEASE #:

UIC #:

CNTY: ADAMS

STATE: CO

SPUD: 6/13/1981

COMP: 9/29/1981

STATUS: PR

WBD DATE: 10/14/2022

FTG:

Q-Q: NESW

SEC.: 19

TWS: 1S

RGE: 64W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5189 '

KB: 10 '

GLE: 5179 '

TD (ft): 8050

PBTD (ft): 8033

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>214</u>
<u>7 7/8</u>	<u>5 1/2</u>	<u>15.5</u>		<u>0</u>	<u>8050</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>J SAND</u>	<u>7926</u>	<u>7956</u>	<u>124</u>		

12.25" Hole
8.625" 24# Csg @ 214 '
Cmt'd w/250 sxs

SLIDING SLEEVE @ 1385 '
(Cmt vol not rpt'd)

TOC @ 6722 '
Calc Assuming 1.15 yield

7.875" Hole
5.5" 15.5# Csg @ 8050 '
Cmt'd w/200 sxs

J SAND Perfs
7926'-7956'

PBTD (ft): 8033 '

TD (ft): 8050 '