

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 42 PAN AM D #2

FIELD: SPINDLE

API # 05-123-10299

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 5/26/1981

COMP: 9/26/1981

STATUS: SI

WBD DATE: 10/14/2022

FTG:

Q-Q: NWNE

SEC.: 21

TWS: 2N

RGE: 66W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 4981 '

KB: 10 '

GLE: 4971 '

TD (ft): 4853

PBTD (ft): 4796

12.25" Hole  
8.625" 24# Csg @ 211 '  
Cmtd w/200 sxs

TOC @ 3591 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 4853 '  
Cmtd w/250 sxs

SUSSEX Perfs  
4708'-4738'

PBTD (ft): 4796 '

TD (ft): 4853 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>211</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4853</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4708</u>	<u>4738</u>	<u>62</u>		