

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 42 PAN AM E #6

FIELD: SPINDLE

API # 05-123-08789

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/13/1976

COMP: 8/31/1976

STATUS: PR

WBD DATE: 10/14/2022

FTG:

Q-Q: NWSW

SEC.: 3

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4965 '

KB: 8 '

GLE: 4957 '

TD (ft): 4805

PBTD (ft): 4765

12.25" Hole
8.625" 24# Csg @ 779 '
Cmtd w/600 sxs

TOC @ 3796 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4806 '
Cmtd w/200 sxs

SUSSEX Perfs
4638'-4680'

PBTD (ft): 4765 '

TD (ft): 4805 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>779</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4806</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4638</u>	<u>4680</u>	<u>86</u>		