

OPERATOR: **K.P. Kauffman Company Inc.**

WELL: **COSSLETT A #9**

FIELD: **SPINDLE**

API #: **05-123-09157**

LEASE #:

UIC #:

CNTY: **DACONO/WELD**

STATE: **CO**

SPUD: **4/5/1977**

COMP: **6/29/1977**

STATUS: **SI**

WBD DATE: **10/17/2022**

FTG:

Q-Q: **SESE**

SEC.: **2**

TWS: **1N**

RGE: **68W**

BY:

## CURRENT WELLBORE DIAGRAM

KBE: **5019'**

KB: **10'**

GLE: **5009'**

TD (ft): **5280'**

PBTD (ft): **5225'**

12.25" Hole

8.625" 24# Csg @ **808'**

Cmtd w/575 sxs

TOC @ **3247'**

Calc Assuming 1.15 yield

7.875" Hole

4.5" 10.5# Csg @ **5266'**

Cmtd w/400 sxs

SUSSEX Perfs

4684'-4708'

SHANNON Perfs

5130'-5148'

PBTD (ft): **5225'**

TD (ft): **5280'**

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	808
7 7/8	4 1/2	10.5		0	5266

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4684	4708	50		
SHANNON	5130	5148	38		