

OPERATOR: K.P. Kauffman Company Inc.

WELL: SELTZER FARMS A #2

FIELD: SPINDLE

API # 05-001-08283

LEASE #:

UIC #:

CNTY: ADAMS

STATE: CO

SPUD: 6/9/1983

COMP: 9/25/1983

STATUS: SI

WBD DATE: 10/27/2022

FTG:

Q-Q: NWNW

SEC.: 3

TWS: 1S

RGE: 67W

BY:

### CURRENT WELLBORE DIAGRAM

KBE: 5108 '

KB: 8 '

GLE: 5100 '

TD (ft): 5100

PBTD (ft): 5050

12.25" Hole  
8.625" 24# Csg @ 1133 '  
Cmtd w/600 sxs

TOC @ 3872 '  
Calc Assuming 1.15 yield

7.875" Hole  
5.5" 15.5# Csg @ 5100 '  
Cmtd w/185 sxs

SUSSEX Perfs  
4930'-4990'

PBTD (ft): 5050 '

TD (ft): 5100 '

#### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>1133</u>
<u>7 7/8</u>	<u>5 1/2</u>	<u>15.5</u>		<u>0</u>	<u>5100</u>

#### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

#### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4930</u>	<u>4990</u>	<u>244</u>		