

OPERATOR: K.P. Kauffman Company Inc.

WELL: SIDNEY STREAR #4

FIELD: SPINDLE

API # 05-123-08683

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 4/22/1976

COMP: 6/7/1976

STATUS: PR

WBD DATE: 10/27/2022

FTG:

Q-Q: SWSE

SEC.: 22

TWS: 2N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5010 '

KB: 10 '

GLE: 5000 '

TD (ft): 4820

PBTD (ft): 4772

12.25" Hole
8.625" 24# Csg @ 717 '
Cmtd w/625 sxs

TOC @ 3765 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @ 4775 '
Cmtd w/200 sxs

SUSSEX Perfs
4658'-4686'

PBTD (ft): 4772

TD (ft): 4820

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	717
7 7/8	4 1/2	10.5		0	4775

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4658	4686	58		