

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 42 PAN AM C #1

FIELD: SPINDLE

API # 05-123-07345

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 7/31/1971

COMP: 8/30/1971

STATUS: PR

WBD DATE: 10/28/2022

FTG:

Q-Q: SWSW

SEC.: 27

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 5025 '

KB: 9 '

GLE: 5016 '

TD (ft): 4990

PBTD (ft): 4927

12.25" Hole
8.625" 24# Csg @ 236 '
Cmtd w/200 sxs

TOC @ 2970 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 11.6/10.5# Csg @ 4989 '
Cmtd w/400 sxs

SUSSEX Perfs
4874'-4900'

PBTD (ft): 4927 '

TD (ft): 4990 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	236
7 7/8	4 1/2	11.6/10.5		0	4989

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4874	4900	27		