

OPERATOR: K.P. Kauffman Company Inc.

WELL: UPRR 42 PAN AM D #3

FIELD: SPINDLE

API # 05-123-10300

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 5/30/1981

COMP: 10/24/1981

STATUS: SI

WBD DATE: 10/28/2022

FTG:

Q-Q: SWNE

SEC.: 21

TWS: 2N

RGE: 66W

BY:

## CURRENT WELLBORE DIAGRAM

KBE: 4975 '

KB: 10 '

GLE: 4965 '

TD (ft): 4896

PBTD (ft): 4834

12.25" Hole  
8.625" 24# Csg @ 210 '  
Cmt'd w/200 sxs

STAGE TOOL @ 852 '  
(Cmt vol not rpt'd)

TOC @ 4234 '  
Calc Assuming 1.15 yield

7.875" Hole  
4.5" 10.5# Csg @ 4890 '  
Cmt'd w/130 sxs

SUSSEX Perfs  
4650'-4758'

PBTD (ft): 4834 '

TD (ft): 4896 '

### CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>210</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>4890</u>

### TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

### PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
<u>SUSSEX</u>	<u>4650</u>	<u>4758</u>	<u>124</u>		