



Pioneer Energy Services

DATE: 05/04/2021

LOCATION: Ft. Morgan, CO (Wireline) Todd Young (970) 867-5171

UNIT: P-132

ENGINEER: Filiberto Lopez

TICKET NUMBER: T-SCE-2C0-F1E6

CLIENT INFO	COMPANY: Anadarko Petroleum Corporation			PO#:		
	BILLING ADDRESS: PO Box 4995			CITY: The Woodlands	ST: TX	ZIP: 77387-4995
WELL INFO	WELL NAME: WATERFRONT 11-34		FIELD / BLOCK:		COUNTY / PARISH: Weld	ST: CO - Colorado
	API / OCSG#: 05-123-25541	AFE#:	PRICE ZONE: LAND			Page 1 of 4

CODE	SERVICE DESCRIPTION	QTY	AMOUNT
WIR-STAGE	Setup Charges	1	
320	Full Lube	1	
WIR-STAGE	RIH with 3.62" GR/JB to 7870'.	1	
011	Gauge Ring Run 4-1/2"	1	
WIR-STAGE	RIH with a 4.50" casing CIBP & set @ 7860'.	1	
308	CIBP (10K) 4-1/2"	1	
315	Set @ 7860'	1	
WIR-STAGE	RIH with bailer & dump cement on top of CIBP set @ 7860'.	1	
026	Dump Bailer run + SX	1	
WIR-STAGE	RIH with a 4.50" casing CIBP & set @ 7170'.	1	
308	CIBP (10K) 4-1/2"	1	
315	Set @ 7170'	1	
WIR-STAGE	RIH with bailer & dump cement on top of CIBP set @ 7170'.	1	
026	Dump Bailer run + SX	1	
WIR-STAGE	RIH with one perf gun & shoot 16 sqz holes @ 2500'-04'.	1	
330	4 spf/4' 16 total shots, 20 gm charge, 0.71" EH, 7.72" PEN.	1	
WIR-STAGE	RIH with one perf gun & shoot 16 sqz holes @ 2000'-04'.	1	
330	4spf/4' 16 total shots, 20 gm charge, 0.71"EH, 7.72" PEN.	1	