

Ranger Energy Services, LLC  
10350 Richmond Avenue Suite 550  
Houston, TX 77042  
(713) 935-8900  
(713) 935-8901 (FAX)



491324

Unit # C1003

Daily Work Ticket

Day # 16

<b>Customer Name</b>	<b>Customer AFE #</b>	<b>Date:</b>
Chevron	A2681	11/16/2022

<b>Mailing Address</b>	<b>City</b>	<b>State</b>	<b>Zip</b>	<b>County</b>
		CO		Weld County, CO

<b>Field</b>	<b>Lease</b>	<b>Well</b>	<b>Order #</b>
		MCWILLIAMS 15-35	
<b>TVD</b>	<b>MD</b>	<b>Calculated Horizontal Length</b>	<b>Company Rep</b>
00	00	0	Patricia Albidrez

<b>Work Description</b>	
P&A	<input checked="" type="checkbox"/>

<b>Sub Code Description</b>	
Cement	<input checked="" type="checkbox"/>

Description	Qty	Rate	Disc	Total	Stage
Turnkey Rigless Cement Pump Charge					
Water Bobtail Hours					
Cement Retarder					
Cement Defoamer					
Cement (neat)					
Sugar					

<b>Description of Work</b>	<b>Start Time</b> 07:30 AM	<b>Stop Time</b> 05:00 PM
----------------------------	----------------------------	---------------------------

From	To	Hours	Description	Details	Stage
7:30:00 AM	8:00:00 AM	0.5	RU/RD cement crew	(WBS: A2681) C1003 - Patricia Albidrez Gate to gate: 7:30 am – 3:00 pm MOB to location, spot in, rig up, waited on flowback to incinerate gas, 11:30 A	
8:00:00 AM	9:00:00 AM	1	RU/RD cement crew	M Status: 2-3/8" 4.7# EOT at 7,242' inside 4-1/2" 11.6# casing, pumped 34 bbls of freshwater, pumped 1 bbl. LCM pill, displaced with 27.2 bbls, waite	
9:00:00 AM	10:00:00 AM	1	RU/RD cement crew	d 30 minutes, established circulation with 52 bbls of water, pumped 125 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 15	
10:00:00 AM	11:00:00 AM	1	RU/RD cement crew	.8# 1.15 cu.ft./sack Class G cement with retarder, 7.2 bbls of slurry, displaced with 26.7 bbls to cover from 7,242' to 6,729', RD valve, wash out pum	
11:00:00 AM	5:00:00 PM	6	RU/RD cement crew	p; 2:00 MOB to yard Non rev: pre/post-trip trucks, prep for job, clean yard, clean pickups	

Payroll Section					
Employee	Rev Hours	Travel Hours	Non Rev Hours	Total	
Supervisor Pena, Marcos	7.50	0.00	0.50	8.00	
Operator Meza, Abraham	7.50	0.00	2.00	9.50	
Derrick Soto, Juan I.	7.50	0.00	2.00	9.50	

No Unreported Incidents Per My  
Signature

Ranger Representative

Customer/Agent

