

Donnelly Casing Pulling Co. RECEIVED

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751



Donnelly

COLORADO OIL & GAS CONS. COMM.
INVOICE DATE 11-10-80

SOLD TO

E. Doyle Huckabay, Ltd.
c/o Mr. R. L. Comer
Box 56
Ft. Morgan, Colorado 80701

WELL

Amoco Maddern #1

INVOICE NO. 062

QVR	✓
FJP	
MM	✓
JAM	✓
JJD	✓
QD	
QDM	

Pulled rods & Tubing		\$ 750.00
4211' 5½" OD Casing @	60¢ per foot	2526.60
Day Work, 58 hours @	\$40.00 per hour	2320.00
Cement, 30 sacks @	\$5.50 each + tax	169.95
Pump Job, 1 @	\$500.00 per job	500.00
Water Truck, 6 hours @	\$35.00 per hour	210.00
Welder, 4 hours @	\$21.00 per hour	84.00
		<u>\$6560.55</u>

11005-29

DATE	DAY WORK	REMARKS
9-8-80	0 hours	Moved rig. Raised mast. Hooked up lines. Worked rods loose. Started pulling.
9-9-80	0 hours	Finished pulling rod. Started pulling tubing.
9-10-80	0 hours	Finished pulling tubing.
9-11-80	12 hours	Ran sand to 6200'. Dug cellar. Set in jacks. Worked pipe to 48". Loaded hole. Dumped 5 sacks cement on sand at 6200'. Shot at 5200'. Water truck, 6 hours.
9-12-80	9 hours	Worked pipe to 52". Shot at 5100'. Worked pipe to 54".
9-15-80	5 hours	Worked pipe at 54". Loaded junk rack. Lowered poles. Moved off.
9-17-80	0 hours	Pumped 50 bbl oil down casing, at 2500#. Followed with 130 bbl water. Last 30 bbl water pumped at 1500#. Pump Job.
10-24-80	0 hours	Moved rig back on well.
10-27-80	9 hours	Raised mast. Set in jacks. Worked pipe to 50".
10-28-80	10 hours	Worked pipe to 56". Shot at 5000', 4700' and 4500'. Worked pipe at 56".
10-29-80	9 hours	Worked pipe at 57". Shot at 4300' and 4000'. Worked loose. Pulled 10 joints.
10-20-80	0 hours	Pulled 50 joints.
✓ 10-31-80	4 hours	Finished pulling casing, 136 total. Set 15 sacks cement in and out bottom of 8 5/8" at 267'. Mud-dred to 35". Set 10 sacks cement to 3' below ground level. Cut off surface. Welded on plate.

RECEIVED NOV 21 1980

R. L. Comer

All open accounts are due by 10th of month following purchase. All amounts 30 days past due will be charged a FINANCE CHARGE at 1½% per month or an ANNUAL PERCENTAGE RATE of 18%.

WELL COMPLETE