

Donnelly Casing Pulling Co.

RECEIVED

OCT 3 1 1988

Phone 522-1410

P.O. Box 791
Sterling, Colorado 80751

COLO. OIL & GAS CONS. COMM. Bob Donnelly

SOLD
TOE. Doyle Huckabay, Ltd.
1706 Security Life Bldg.
Denver, Co. 80202

INVOICE DATE 8-09-88

WELL

Amoco #43-27

INVOICE NO. 88-463

THIS IS NOT AN INVOICE. FOR INFORMATION ONLY.

3525' 5½" OD Casing @	\$.60 per foot	\$2115.00
Day Work, 36 hours @	\$ 50.00 per hour	1800.00
Cement, 45 sacks @	\$ 7.50 each + tax	347.63
Shots, 4 @	\$ 30.00 per shot	120.00
Water Truck, 6 hours @	\$ 38.00 per hour	228.00
Welder, 4 hours @	\$ 21.00 per hour	84.00
Hauled casing to our yard:		
Mack Truck, 8 hours @	\$ 42.00 per hour	336.00
Trailer, 8 hours @	\$ 10.00 per hour	80.00
Pump Job, 1 @	\$550.00 per job	550.00
		<u>\$5660.63</u>

DATE	DAY WORK	REMARKS
7-19-88	11 hours	Moved unit in. Dug deadmen and cellar.
7-20-88	16 hours	Ran sand from 6283' to 6175'. Loaded hole. Set in floor. Worked pipe to 48". Dumped 5 sacks cement on sand. Water truck, 6 hours.
7-21-88	10 hours	Ran shots to 4800', 4420', 4010' and 3525'. Came loose. Pulled 1 joint.
7-22-88	0 hours	Pulled 87 joints casing.
7-25-88	5 hours	Pulled pipe. Tore out floor. Pumped 35 sacks cement at 385'. Filled with mud to 15'. Set 5 sacks cement in top. Cut off surface. Welded on cap. Pump job.

WELL COMPLETE

THANK YOU