


OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO



PLUGGING RECORD



INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Plains Exploration Company Field Pierce Wildcat  
 Lease Name R. B. Smoot Well No. # 1 County Weld  
 Location C SW SW Section 10 Township 8 N Range 66 W Meridian 6th  
 (Quarter Quarter)  
660 feet from S Section line and 660 feet from W Section Line  
 N or S E or W

TOTAL DEPTH	<u>9429</u>	DATE OF PLUGGING	<u>(1957) December 15th, 1957</u>
-------------	-------------	------------------	-----------------------------------

DETAILS OF WORK

The well was plugged December 15th, 1957 by filling it with heavy mud from the total depth to the bottom of the surface pipe (9429 to 498). A 20 sack cement plug was set in the bottom 30 feet of the surface pipe (498 to 468), then the casing was filled with heavy mud to within 20 feet of the top. A 10 sack cement plug was set in the top 20 feet of the surface pipe (34 to 14). All measurements are taken from the kelly bushing which was approximately 12 feet above the ground.

AJJ	
DVR	
FJK	
HH.A.	
AH	
JJD	
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: \_\_\_\_\_ Date DEC 19 1957  
 Company Plains Exploration Company Date Dec. 17th, 1957  
 1135 Petroleum Club Bldg.  
 Address Denver 2, Colorado. Phone No. PH -CH 4-7431  
 By Russell H. Volk Title President  
 Director \_\_\_\_\_ (Signature)