

Ranger Energy Services, LLC
10350 Richmond Avenue Suite 550
Houston, TX 77042
(713) 935-8900
(713) 935-8901 (FAX)



501180

Unit # C1003

Daily Work Ticket

Day # 8

Customer Name	Customer AFE #	Date:
Chevron	A2845	12/8/2022

Mailing Address	City	State	Zip	County
		CO		Weld County, CO

Field	Lease	Well	Order #
		JOHNSON, VERN 1-A	
TVD	MD	Calculated Horizontal Length	Company Rep
00	00	0	Patricia Albidrez

Work Description	
P&A	<input checked="" type="checkbox"/>

Sub Code Description	
Cement	<input checked="" type="checkbox"/>

Description	Qty	Rate	Disc	Total	Stage
Turnkey Rigless Cement Pump Charge			0.00%		
Wireline Charge			0.00%		
Water Bobtail Hours			0.00%		
Water			0.00%		
Cement Retarder			0.00%		
Cement (neat)			0.00%		
Sugar			0.00%		
Cement Defoamer			0.00%		

Description of Work Start Time 05:30 AM Stop Time 06:30 PM

From	To	Hours	Description	Details	Stage
5:30:00 AM	6:00:00 AM	0.5	RU/RD cement crew	(A2845) C1003 - Patricia Albidrez Gate to gate: 6:30am – 1:00 PM MOB to location, spot in, rig up, waited on flowback to incinerate gas, 9:00 AM Statu	
6:00:00 AM	6:30:00 AM	0.5	RU/RD cement crew	s: 2-3/8" 4.7# EOT at 6572' inside 4-1/2" 11.6# casing, pumped 31 bbls of freshwater, pumped 4 bbl. LCM pill, displaced with 24.6 bbls, waited 30 min	
6:30:00 AM	7:00:00 AM	0.5	RU/RD cement crew	utes, established circulation with 51 bbls of water, pumped 103 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 36 sxs of 15.8# 1.15	
7:00:00 AM	7:30:00 AM	0.5	RU/RD cement crew	cu.ft./sack Class G cement with retarder, 7.3 bbls of slurry, displaced with 24.5 bbls to cover from 6572' to 6059', PH 7.2 Chlorides: <150 ppm, Tempe	
7:30:00 AM	8:00:00 AM	0.5	RU/RD cement crew	rature: 56 F ,RD valve, wash out pump; 12:15 MOB to yard Non rev: pre/post trip trucks, prep for job, boost pump packing, Patrick, witches hat, change	
8:00:00 AM	6:30:00 PM	10.5	RU/RD cement crew	oil on bobtail	

Payroll Section					
Employee	Rev Hours	Travel Hours	Non Rev Hours	Total	
Supervisor	Pena, Marcos	6.50	0.00	4.50	11.00
Operator	Diaz, Luis M.	6.50	0.00	6.50	13.00
Derrick	Meza, Abraham	6.50	0.00	4.50	11.00
FloorHand	Soto, Juan I.	5.00	0.00	0.00	5.00

No Unreported Incidents Per My
Signature

Ranger Representative

Customer/Agent

Ranger Energy Services LLC and its customer acknowledge and agree that in the absence of an executed master service agreement, Ranger's Terms and Conditions will govern all services performed by Ranger including the allocation of liability for events occurring on location. A current copy may be obtained by email at Contracts@RangerEnergy.com or by calling 713.935.8906.