


OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADOOIL & GAS  
CONSERVATION COMMISSION

## PLUGGING RECORD

## INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Vincent & Welch, Inc. Field \_\_\_\_\_ Wildcat Yes  
Lease Name N. J. Meagher Well No. 1 County \_\_\_\_\_ Routt \_\_\_\_\_  
Location SE SW Section 31 Township 8N Range 87W Meridian 6th P  
(Quarter Quarter)  
430 feet from S Section line and 1897 feet from W Section Line  
Nor S E or W

TOTAL DEPTH 5330'DATE OF PLUGGING Dec. 19, 1959*Verbal  
12/18/59*

## DETAILS OF WORK

Spudded Nov. 20, 1959. Drilled 12½" hole. Set 308' 8-5/8" 28# N80 casing on Nov. 21 with 180 sx. cement plus 2% CaCl. Drilled out from surface pipe 7:00 P. M. Nov. 22, 1959. Drilled 7-7/8" hole to total depth of 5330'. Finished drilling Dec. 17, 1959. Hole left full of 10#, 55 viscosity mud containing 10% No. 2 diesel oil. Plugged Dec. 19, 1959 with 50 sx. regular neat cement from, 360-280 feet and from 75 feet to ground level. Marked location with 4" drill pipe 10' long of which 4' extends above ground level. Welded cap on pipe.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date DEC 30 1959

Director

Company Vincent & Welch, Inc. Date Dec. 28, 1959Address 1507 Denver Club Bldg. Phone No. AL 5-0404By Ray L. Chambers Title Vice President  
(Signature)