

Well Name: BAIN 01 (05191)

API # 0512305191	Surface Legal Location NWNW 12 5N61W 6	Field Name	Permit Number	State CO	Well Configuration Type
Ground Elevation (ft) 4,639.00	Casing Flange Elevation (ft)	Orig KB-Ground Distance (ft) 0.00	KB-Casing Flange Distance (ft)	Surface Spud Date	Final Rig Release Date

Job: Abandon Well / &lt;jobsubtyp&gt; , 12/4/2022 06:00, P1657C

Job Category Abandon	Primary Job Type Abandon Well	Secondary Job Type
Start Date 12/4/2022	End Date 12/7/2022	
Objective		

## SUMMARY

Rpt #	Start Date	End Date	24 Hr Summary	REMARKS/ISSUES
1.0	12/4/2022	12/5/2022	TRANSPORT RIG & EQUIPMENT TO LOCATION, SAFETY MEETING, INSPECT RIG, MIRU, NIPPLE UP & TEST BOPE, RIH W/ 7-7/8" JETTED ROCK BIT, TAG & START WASHING DOWN @ 240' WASH DOWN TO 1800'	
2.0	12/4/2022	12/5/2022	SAFETY MEETING, LOAD & TRANSPORT EQUIPMENT TO LOCATION, INSPECT RIG, RIG UP, N/U BOP CHANGE PIPE RAMS BACK TO 5 1/2", TEST BOP, START DRILLING W/ 7-7/8 JETTED TRI -CONE, CON'T DRILLING, FIRST TAG @ 240', DRILLDOWN TO 350' W/ GOOD CUTTINGS COMING OVER SHAKER, CONTINUE DRILLING TO 1500' ON TOWER CHANGE	
3.0	12/5/2022	12/6/2022	CONTINUE DRILLING FROM 1500' TO 5032', TORQUE UP ON CSG DOWN HOLE, METAL SHAVINGS COMING ACROSS SHAKER, GET IN TOUCH WITH STATE, CHANGE PLUG DEPTH PER STATE, TOO H TO CHANGE DRILL BIT, RIH WITH CMT DRILL BIT, WASH DOWN TO 4823'	
4.0	12/5/2022	12/6/2022	WASH DOWN FROM 1800' TO 5032' TAG W/HIGH TORQUE CIRC BOTTOMS RECOVER METAL SHAVINGS & DIME SIZE PIECES OF METAL, DECISION MADE TO POOH, POOH L/D HWDP REMOVE FLOAT, CHANGE BITS, RBIH WASHING DOWN EVERY JT TO 3000'	
5.0	12/6/2022	12/7/2022	CONTINUE WASHING DOWN TO TD @ 5032', CIRCULATE A HIGH VIS SWEEP, CIRCULATE 2 BOTTOMS UP, MIRU CMT CREW, CEMENT WITH 75SKS OF G CMT W/ CMT RETARDER 15.8#/GAL (15.5BBL), 1.15 YIELD, WR 5.0GAL/SK, FROM 5032'-4832', TOO H 15 JTS, CIRCULATE WELL, TOO H TO 2200', CIRCULATE WELL, MONITOR WELL FOR MIGRATION, CEMENT WITH 90SKS OF THIXSO CMT (21.5BBL), 15.2#/GAL, 1.32 YIELD, WR 5.9GAL/SK, FROM 2200'-2000', TOO H WITH 10 JTS, CIRCULATE WELL, WOC 3 HRS, TAG TOC @ 1925', TOO H TO 800', CIRCULATE WELL, MONITOR WELL FOR MIGRATION, CEMENT WITH 900SKS OF G CMT (184BBL), 1.15 YIELD, WR 5.0GAL/SK, FROM 800'-0', TOO H, TOP OFF WELL, RDMO	
6.0	12/7/2022	12/8/2022	TOP OFF WELL WITH 30SKS (6BBL) G CMT, 1.15 YIELD, 5.0 GAL/SK, TOP WELL OFF TO SURFACE	
7.0	12/15/2022	12/15/2022	BAIN 01 (05191) WAS CUT AND CAPPED ON 12/15/2022. CUT AT 6'7" DEPTH.	